

ITEM 463

SAFETY END TREATMENT

463.1 Description. This item shall govern for the materials to be furnished and for the construction of Safety End Treatment (S.E.T.) for drainage structures at the designated locations, in accordance with this item and as shown on the construction drawings.

463.2 Materials. Unless otherwise shown on the drawings, materials shall conform to the following:

Item 420, "Concrete Structures"

Item 421, "Structural Concrete"

Item 440, "Reinforcing Steel"

Item 460, "Reinforced Concrete Pipe"

Item 461, "Corrugated Metal Pipe"

Item 480, "Precast Reinforced Concrete Box Sewers"

Pipe Runners - ASTM A53, Grade B or equivalent strength pipe

Plates and Angles - ASTM A36

Bolts and Nuts - ASTM A307

Unless otherwise shown on the drawings, all metal pipe, plates, angles, nuts and bolts shall be galvanized in accordance with ASTM A123, or A153, whichever is pertinent.

463.3 Types of Safety End Treatment

A. Parallel Drainage Safety Pipe Runners (PD-SPR) PD-SPR type I shall be used on single or multiple reinforced concrete box culvert (RCB), either precast or cast in place, or type II reinforced concrete pipe (RCP) or corrugated metal pipe (CMP) with the ends tapered to the proper slope as shown on Texas Department of Transportation (TxDOT) standard drawing B16, unless shown otherwise in the Contract Documents.

B. Cross Drainage Safety Pipe Runners (CD-SPR) CD-SPR type I shall be used on single or multiple reinforced concrete box culvert (RCB), either precast or cast in place, or type II reinforced concrete pipe (RCP) or corrugated metal pipe (CMP) with the ends tapered to the proper slope as shown on Texas Department

of Transportation (TxDOT) standard drawing, unless shown otherwise in the Contract Documents.

Unless otherwise shown on the drawings, when CMP or RCP is specified for the pipe structure, the contractor shall have the option of providing prefabricated metal end sections or precast S.E.T. units in place of mitered CMP or RCP.

- 463.4 Construction. Construction shall be in accordance with the details shown on the drawings and in accordance with the construction and installation methods of General Specifications Items 420, 430, 433, 461, and 480, whichever apply.

Damaged galvanizing shall be repaired by the contractor in accordance with Item 461.

When required riprap, paving headwall or collars are to be installed. They shall be in accordance with Item 491, "Reinforced Concrete Slope Paving".

Any required structural excavation shall be in accordance with Item 400, "Structural Excavation and Backfill". Removal of portions of in-place structures when required, shall be in accordance with item 495, "Removing Old Structures". The extension of concrete structures, when required, will be in accordance with Item 424, "Extending Concrete Structures".

- 463.5 Measurement. S.E.T. will be measured by each unit of size specified with or without PD-SPR or CD-SPR.

Structural excavation and any slope paving headwalls or collars required by the drawing will not be measured but will be considered subsidiary to this item.

- 463.6 Payment. Payment for S.E.T. will be paid for at the unit price bid for each for the particular size as measured herein. The following shall be specified for each S.E.T.:

S.E.T. (Type I)(Height)(Slope) or
S.E.T. (Type I)(Height)(Slope) (Orientation);
S.E.T. (Type II)(Pipe Size)(Pipe Material)(Slope) or
S.E.T. (Type II)(Pipe Size)(Pipe Material)(Slope)(Orientation).

This payment shall be full compensation for the breaking and removing of all concrete, when required, removing a portion of in-place structures

and extending concrete structures, when required, for all concrete, reinforcing steel, CMP, RCP, RCB slope paving, toe wall, concrete aprons, pipe runners, collars, nuts, riprap₂, bolts, plates and angles as may be required, for all structural excavation, galvanizing, for all labor, tools, equipment, for construction or furnishing and installing S.E.T. units and incidentals necessary to complete the work. If the S.E.T. is specifically to be pre-cast, it shall be noted as such.

There are line code(s), description(s), and unit(s) for this item.

Note: This specification requires drawings (TxDOT standards) that are downloadable on TxDOT's web-site.

END OF ITEM 463

SUMMARY SHEET

ITEM 463 - SAFETY END TREATMENT

Other Specifications Required

Item 420, Concrete Structure

Item 421, Concrete

Item 440, Reinforcing Steel

Item 460, Reinforced Concrete Pipe

Item 461, Corrugated Metal Pipe

Reference Standards

1. ASTM A53
2. ASTM A307
3. ASTM A36
4. ASTM A123
5. ASTM A153
6. ASTM A307

Description

This item discusses the requirements for and the installation of safety end treatment section.

Payment

By each size specified with or without parallel or cross drainage safety pipe runners.

DO NOT INCLUDE THIS SHEET IN THE CONTRACT SPECIFICATIONS.